

**GOVERNMENT OF WEST BENGAL
OFFICE OF THE DEPUTY COMMISSIONER OF POLICE
RESERVE FORCE, KOLKATA POLICE
STANDARD BUILDING, 32, B.B.D BAG, KOLKATA - 700 001**

**NOTIFICATION ON NOTICE BOARD
H.A.R.F. 32, B.B.D BAG**

NIQ No. 02 /HARF/MW


Dt. 29.07.2022

NOTICE INVITING QUOTATION

Sealed **SPOT QUOTATIONS** are invited by the Dy. Commissioner of police Reserve Force, Kolkata from the willing firms for emergent repairing of damaged staircase of 'E' Coy RF at 438, Jessore Road, Patipukur, Kolkata-700048.

| S.L No | Description of work | Quantity |
|--------|---|--------------|
| 1 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corner as directed and raking out joints including throating, noising and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] iii) with 1:3 cement mortar b) 15mm thick plaster. | 38.58 sqmtr |
| 2 | Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 Cement) as per manufacturer's specification [Cement to be supplied by the Department] | 38.58 sqmtr |
| 3 | Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic (as per manufacturer's specification) including cleaning and smoothing of surface. Two coats | 225.94 sqmtr |

- The price should be quoted inclusive of all taxes and GST.
- Willing firms having necessary & sufficient financial capability and experience (Authorized contractor) in this type of work /supply may submit their Quotations to H.A.R.F. Office, within 7 (seven) working days from the date of issue of this notice by super scribing on the envelop as "Quotation in response to NIQ No. 02/HARF/MW Date....."
- The authority reserves the right to reject any or all the quotations without assigning any reason in this regard.
- Lowest accepted rate in this quotation will valid for next six months or till further orders.
- Firms/Agencies who are willing to comply with the above criteria only should Submit rate.


**Deputy Commissioner of Police
Reserve Force, Kolkata.**

**Deputy Commissioner of Police,
Reserve Force, Kolkata**



Estimate

Name of work: Emergent repairing of damaged staircase for "E" company,RF at 438, Jessore Road, Patipukur, Kolkata.700048 during the year 2022-2023

| Sl No | Page & Item No | Description of item | Qty | Rate | Unit | Amount |
|-------|---------------------|--|----------------|-------|-------|-------------------------|
| 1 | Page-189 Item-1 | Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (iii) With 1:3 cement mortar (b) 15 mm thick plaster | | | | |
| 2 | Page-45 Item-8 | (a) Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification [Cement to be supplied by the Department] | 28.58 38.58 | | sqmtr | 150.00 88.00 |
| 3 | Page-196 Item-10 | Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats | 225.94 | 70.00 | sqmtr | 15815.80 |
| | | | | | | 26155.24 |
| | | | | | | Add 6% for CGST 1569.31 |
| | | | | | | Add 6% for SGST 1569.31 |
| | | | | | | Total 29293.87 |
| | | | | | | Say Rs 29294.00 |

(Rupees Twenty Nine Thousand Two Hundred and Ninety Four Only)

Technically Checked & Verified
by
[Signature] 09/July/22
Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal