

**GOVERNMENT OF WEST BENGAL
OFFICE OF THE DEPUTY COMMISSIONER OF POLICE
RESERVE FORCE, KOLKATA POLICE
STANDARD BUILDING, 32, B.B.D BAG, KOLKATA - 700 001**

**NOTIFICATION ON NOTICE BOARD
H.A.R.F, 32, B.B.D BAG**

NIQ No. 04 /HARE/MW


Dt. 29.07.2022

NOTICE INVITING QUOTATION

Sealed SPOT QUOTATIONS are invited by the Dy. Commissioner of police Reserve Force, Kolkata from the willing firms emergent repairing work for 'D' Company R.F. Police Barrack, Khadyabhawan located at 11/A, Mirza Ghalib Street Kolkata-7000087

S.L No	Description of work	Quantity
1	Panel shutters of door and window, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings In ground floor. (In case of non-supply of single plank, penal rate of reduction of 20% will be made) (iv) 25mm thick shutter with 12mm thick panel of size 30 to 45 cm. (b) Sishu, Gamar, Champ, Badam, Bhola, Mogra, Hallak.	5.40sqmtr
2	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corner as directed and raking out joints including throating, noising and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] iii) with 1:3 cement mortar b) 15mm thick plaster.	21.48 sqmtr
3	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic (as per manufacturer's specification) including cleaning and smoothing of surface. Two coats	51.36 sqmtr
4	Supplying, fitting & fixing of PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D. 1785 and threaded to match with G.I. Pipes as per IS: 1239 (part-I) with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paints in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made of accessories, specials. Payment for painting will be made separately) (a) For exposed work PVC Pipes (Dia) 20mm.	7.62 mtr

- The price should be quoted inclusive of all taxes and GST.
- Willing firms having necessary & sufficient financial capability and experience 04(Authorized contractor) in this type of supply may submit their Quotations to the H.A.R.F. Office, within 7 (seven) working days from the date of issue of this notice by super scribing on the envelop as "Quotation in response to NIQ No. 04/HARE/MW Date....."
- The authority reserves the right to reject any or all the quotations without assigning any reason in this regard.
- Lowest accepted rate in this quotation will valid for next six months or till further orders.
- Firms/ Agencies who are willing to comply with the above criteria only should Submit rate.


Deputy Commissioner of Police
Reserve Force, Kolkata.
Deputy Commissioner of Police.
Reserve Force, Kolkata

3

Estimate

Name of work: Emergent repairing work for "D" Company RF Police Barrack, Khadyabhawan located at 11/A, Mirza Ghalib Street, Kolkata-700087 during the year 2022-2023

Sl No	Page & Item No	Description of item	Qty	Rate	Unit	Amount	
1	Page-117 Item-1	Panel shutters of door and window, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings. In ground floor. (In case of non-supply of single plank, penal rate of reduction of 20% will be made)					
		(iv) 25mm thick shutters with 12mm thick panel of size 30 to 45 Cm.					
		(b) Sishu, Gamar, Champ, Badam, Bhola, Mogra, Hallak.	5.40	sqmtr	2259.00	sqmtr	12198.60
2	Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface]					
		(iii) With 1:3 cement mortar					
		(b) 15 mm thick plaster	21.48	sqmtr	180.00	sqmtr	3866.40
3	Page-196 Item-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats	51.36	sqmtr	70.00	sqmtr	3595.20
4	Page-12 Item-19(i) (S & P)	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately)					
		(a) For Exposed Work -- PVC Pipes (Dia) 20 mm	7.62	mtr	129.00	mtr	982.98
						20643.18	
						Add 6% for CGST	1238.59
						Add 6% for SGST	1238.59
						Total	23120.36
						Say Rs	23120.00

(Rupees Twenty Three Thousand One Hundred and Twenty Only)

Technically Checked & Verified

by
09/July/22

Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal