Estimate

Name of work: Estimate for Repairing of Wall plaster with putty and kitchen black stone replacement, door replacement of bathroom and inside painting .at Sukhobrishti ,Rajarhat New town ,QUATER NO.103 1st FL BLOCK NO-D/349. [IBMS Req. No. 2115 Dt: 14/06/2023]

	14/06/2	025					
S1 No	Page & Item No		Quar	ntity	Rate	Unit	Amount
1	Page-11 Item-10	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	15.40	sqmtr	19.00	sqmtr	292.60
2	Page-45 Item-8	a) Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification [Cement to be supplied by the Department]	15.40	sqmtr	88.00	sqmtr	1355.20
3	Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]					
		(ii) With 1:6 cement mortar					
		(c) 15 mm thick plaster	15.4	sqmtr	155	sqmtr	2387.00
4	Page-198 Item-5	Rendering the Surface of walls and ceiling with White Cement base WATER PROOF wall putty of approved make & brand.(1.5 mm thick)	16.90	sqmtr	122.71	sqmtr	2073.80
5	Page-196 Item-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothning of surface. Two Coats	116.50	sqmtr	70.00	sqmtr	8155.00
6	Page-200 Item-1	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc	7.02	sqmtr	29.00	sqmtr	203.58
7	Page-200 Item-1	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	10.20	sqmtr	38.00	sqmtr	387.60
8	Page-200 Item-2	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary :					
		(a) On timber or plastered surface : With super gloss (hi-gloss) -					
		(iv) Two coats (with any shade except white)	10.20	sqmtr	81.00	sqmtr	826.20
		(b) On steel or other metal surface :	10.20	oquiti	01.00	oqiiid	020.20
		With super gloss (hi-gloss) -					
		(iv) Two coats (with any shade except white)	7.03	sqmtr	79.00	sqmtr	555.37
9	Page-152	.,	1.80	sqmtr	126.00	sqmtr	226.80
	Item-31	Taking out shutter of door and window, dismantling by parts (for repair or replacement of damaged parts), reassembling and refitting and rehanging same with old fittings but with new screws as necessary. (Where different parts of same shutter are renewed under different item, payment under item 73 will be made once only).					
10	Page-125 Item-15	Supplying, Fitting & Fixing 30 mm thick Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails, M.S. frame shall have cost of steel primers of approved make and manufacture, M.S. frame covered with 5 mm th. heat moulded PVC "C" channel of size 30 mm th, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on either sides forming styles; and 5 mm th. 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm tapered in 45 degree on the inner side to form top & bottom rail and 115 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel with 10 mm (5 mmx2) th.,20 mm wide cross PVC sheet as gap insert for top rail and bottom rail. Paneling of 5 mm th. both side PVC sheet to be fitted in the M.S. frame welded/sealed to the styles &rails with 7 mm (5 mm+2 mm) th.x15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm th. PVC strip of 20 mm which is to be stuck on the interior side of the "C" channel using PVC solvent adhesive etc. complete excluding all necessary hardwares as per direction of Engineer-in-Charge. In ground floor.	1.80	sqmtr	1957.00	sqmtr	3522.60

¹¹ Page-140 Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.

S1 No	Page & Item No	Description of item	Quantity		Rate	Unit	Amount
12	Page-145 Item-28	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. $2681/66$) fitted and fixed complete.					
13	Page-145 Item-30	$\label{eq:continuous} \begin{tabular}{ll} (i) 250mm x 16mm dia bolt \\ Anodised aliminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete: \\ \end{tabular}$	2.00	each	233.00	each	466.00
		(a) With continuous plate base (Hexagonal / Round rod)					
		(vii) 150 mm grip x 12 mm dia rod.	2.00	each	111.00	each	222.00
15	Page-16 Item-16	$125\ \mathrm{mm}.$ thick brick work with 1st class bricks in cement mortar (1:4) in ground floor	1.50	sqmtr	748.00	sqmtr	1122.00
16	Page-53 Item-15	Supplying, fitting and fixing Black Stone slab used in Kitchen slab, alcove, wardrobe etc. laid and jointed with necessary adhesive Cement mortar (1:2) including grinding or polishing as per direction of Engineer-in -Charge in Ground Floor.					
		(a) Slab Thickness 20 to 25 mm	1.75	sqmtr	655.00	sqmtr	1146.25
@					• • • • • • • • • • • • • • • • • • • •		24731.00
						for CGST	2225.79
					Add 9% for SGST Total = Add 1% for L.W.Cess Grand Total =		2225.79
							29182.58
							291.83
							29474.40
				Say, Rs.			29474.00

RUPEES: TWENTY-NINE THOUSAND FOUR HUNDRED SEVENTY-FOUR ONLY.

JE-III KPD

AE-II KPD