

Government of West Bengal
Office of the Commissioner of Police
18, Lalbazar Street, Kolkata-700 001.

No. T-357/PHE/24-25

Date – 19.02.2025

NOTICE INVITING TENDER

Sealed tenders in printed form are invited for the following work from eligible tenderers as per particulars given below :

1. Name of work : Repairing of ceiling & wall of kitchen , bathroom , bedroom & dining room, window glasses & inside painting including some electrical work for Quarter No. 9, 2nd floor, Block- M of Nowdapara PHE at B.G. Ghosh Road, Kolkata.
(Details in ANNEXURE-A)
2. Eligibility : All bonafide contractors /firms having experience for essential civil/elec. work.
3. Estimated Cost : Rs. 81,092/-
Last date for submission of the tender : 28. 02. 2025 up to 15.00 hrs.
5. Time allowed for completion of work : 10(ten) days after the issue of Work Order
6. The intending tenderers may inspect the site on any working day during office time.
7. The intending tenderers will have to submit copy of valid Certificate of up to date Clearance of Trade License, Professional tax, Income Tax, G.S.T and Credential along with tender papers for the work.
8. Sealed Tender addressed to The Commissioner of Police, 18, Lalbazar Street, Kolkata-700001 may be dropped in the box kept in front of the office of the Officer-in-Charge, Building Section, 2nd floor, Northern Building, 18, Lalbazar Street, Kolkata-700001 before the last date.
9. Sealed tender may also be sent by Registered Post / Speed Post super scribing the envelope as "Tender in response to Tender Notice No. T-357/PHE/24-25 dt. 19.02.2025" so as to reach on or before the last date.


O.C. Buildings(PHE)
Lalbazar, Kolkata.

Annexure-A

Name of work: Estimate for Repairing of ceiling & wall of kitchen, bathroom, bedroom & dining room , window glasses & inside painting and some Electrical work .OF Nawdapara PHE,BG Ghosh Road ,QUATER NO.09 2 nd FL BLOCK NO- M (During the year 2024-2025). [IBMS Req. No. 1185 Dt: 28/07/2022]

Sl No	Page & Item	Description of item	Quantity	Rate	Unit	Amount	
1	Page-11 Item-10	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	7.00	sqmtr	19.00	sqmtr	133.00
2	Page-40 Item-27	Cement concrete (1:1.5:3) with graded stone chips 45 mm size with hexagonal square mesh wire netting I.R.C. fabric mesh or X.P. M. fitted and fixed affecting the existing reinforcement on concrete without distributing the same and with proper scarping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement including the cost of wire netting I.R.C or X. P. M. & cost of all handling and scaffolding complete as per direction of Engineer-in -charge.					
		b) 25 mm thick	3.00	sqmtr	522.00	sqmtr	1566.00
3	Page-45 Item-08	a) Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification [Cement to be supplied by the Department]	10.00	sqmtr	88.00	sqmtr	880.00
4	Page-45 Item-05	Cleaning the concrete surface by removing dirt and debris, marking defective locations and removing loose concrete by careful stripping untill hard surface is exposed, cutting the concrete to regular shape, wire brushing the exposed surface and removing debris from site complete as per direction of the Engineer - in - Charge	3.00	sqmtr	90.00	sqmtr	270.00
5	Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface]					
		(i) With 1:6 cement mortar					
		(c) 15 mm thick plaster	7.00	sqmtr	151.00	sqmtr	1057.00
		(ii) With 1:4 cement mortar					
		(c) 10 mm thick plaster	3.00	sqmtr	133.00	sqmtr	399.00
6	Page-204 Item-05	(b) Rendering the surface of walls and ceiling with white cement based wall putty of approved make and brand (1.5mm thick)	10.00	sqmtr	110.00	sqmtr	1100.00
7	Page-196 Item-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats	135.00	sqmtr	70.00	sqmtr	9450.00
8	Page-53 Item-15	Supplying, fitting and fixing Black Stone slab used in Kitchen slab, alcove, wardrobe etc. laid and jointed with necessary adhesive Cement mortar (1:2) including grinding or polishing as per direction of Engineer-in -Charge in Ground Floor					
		(a) Slab Thickness 20 to 25 mm	2.00	sqmtr	643.00	sqmtr	1286.00
9	Page-205 Item-01	Supplying best Indian sheet glass panes set in putty and fitted and fixed with nails and putty complete. (In all floors for internal wall & upto 6 m height for external wall)					
		(i) 3 mm thick (weighing 7.4 kg/Sq.m)	0.70	sqmtr	477.00	sqmtr	333.90
10	Page-10 Item-2	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. In ground floor including roof					
		(a) upto 150 mm. thick	0.30	sqmtr	939.00	sqmtr	281.70
11	Page-24 Item-1	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes.					
		a) Pakur Variety	0.30	Cu.M.	5248.57	Cu.M.	1574.57
12	Page-64 Item-35	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work. & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc.					
		(A) Floor With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (i) Coloured decorative	7.00	sqmtr	755.00	sqmtr	5285.00

Page & Item	Description of Item	Quantity	Rate	Unit	Amount
	(B)Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m (a) Area of each tile upto 0.09 Sq.m	24.00	757.00	sqmtr	18168.00
13 Page-152 Item-30	(i) Coloured decorative Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refitting the same including mending good all damages complete. (Concrete and brick work for mending damage will be paid separately)	4.00	119.00	sqmtr	476.00
14 Page-117 Item-1	(a) Upto area 2.5 Sq.m Panel shutters of door and window, as per design (each panel consisting of single plank without joint) including fitting and fixing the same in position but excluding the cost of hinge and other fittings. In ground floor. (In case of non-supply of single plank, penal rate of reduction of 20% will be made) (iv) 25mm thick shutters with 12mm thick panel of size 30 to 45 cm.	1.60	2259.00	sqmtr	3614.40
15 Page-140 Item-5	(b) Sishu, Gamar, Champ, Badam, Bhoia, Mogra, Hallak. Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. (iv) 75mm. X 47mm. X 1.70mm. vi) 100mm. X 50mm. X 1.25mm.	4.00	31.00	each	124.00
16 Page-141 Item-10	i) Iron haap bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with centre bolt and round fitting. (b) 250mm long.	12.00	43.00	each	516.00
17 Page-145 Item-28	ii) Iron haap bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with centre bolt and round fitting. (b) 250mm long.	4.00	159.00	each	636.00
18 Page-145 Item-30	Anodised aluminium Aldrop / Sliding bolts of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 2681/66) fitted and fixed complete. (i) 250mm x 16mm dia bolt	2.00	233.00	each	466.00
	Anodised aluminium D-type handle of approved quality manufactured from extruded section conforming to I.S. specification (I.S. 230/72) fitted and fixed complete: (a) With continuous plate base (Hexagonal / Round rod) (vii) 150 mm grip x 12 mm dia rod.	2.00	111.00	each	222.00
19 Page-16 Item-16	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	2.00	736.00	sqmtr	1472.00
20 Page-200 Item-1	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc	16.00	29.00	sqmtr	464.00
21 Page-200 Item-1	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	28.00	38.00	sqmtr	1064.00
22 Page-200 Item-2	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (a) On timber or plastered surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	28.00	81.00	sqmtr	2268.00
	(b) On steel or other metal surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	16.00	79.00	sqmtr	1264.00
23 Page-81 Item-10	S & P Supplying, fitting and fixing Closet seat of approved make with lid and C.P.hinges, rubber buffer and brass screws complete (a) E.W.C (ii) Plastic (hallow type) white	1.00	380.00	each	380.00

Sl No	Page & Item	Description of item	Quantity	Rate	Unit	Amount	
						1015.00	
4	Page-36 Item-02	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.	1.00	each	1015.00	each	1015.00
25	Page-03 Item-03	Supplying, fitting and fixing shower of approved brand and make	1.00	each	309.00	each	309.00
		(a)(iii) Chromium plated shower arm 240 mm long (Equivalent to Code No. 536(A) & Model - Tropical / Sunthing Special of BSSCO or similar brand)	1.00	each	154.00	each	154.00
		(b) Polythene overhead shower of approved make 15 mm X 125 mm	1.00	each	3285.00	each	3285.00
26	Page-12 Item-06	Supplying, fitting and fixing stainless steel sink complete with waste fittings and two coats of painting of C.I. brackets.	1.00	each	613.00	each	613.00
		(a) Sink only					
		(b) 530 mm X 430 mm x 180 mm					
27	Page-82 Item-19	Supplying, fitting and fixing best quality Indian-make mirror 5.5 mm thick with silvering as per I.S.I. specifications supported on fibre glass frame of any colour, frame size 550 mm X 400 mm	1.00	each	475.00	each	475.00
28	Page-82 Item-22	Supplying, fitting and fixing towel rail with two brackets. (iii) 25 mm dia. and 750 mm long	1.00	each	475.00	each	475.00
29	Page-43 Item-09	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia. (iii) 600 mm long	2.00	each	107.00	each	214.00
30	Page-43 Item-10	Supplying, fitting and fixing approved brand 32 mm dia. P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. (iii) 900 mm long	2.00	each	75.00	each	150.00
31	Page-06 Item-07	Supplying, fitting and fixing bib cock or stop cock. (e) PTMT (Polytetra Bib Cock / Stop Cock (Prayag or equivalent) 15 mm	4.00	each	154.00	each	616.00
32	Page-12 Item-19	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - 1). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately)					
		(a) For Exposed Work PVC Pipes (Dia)	6.00	Mtr	101.00	Mtr	606.00
		15mm	3.00	Mtr	177.00	Mtr	531.00
		25mm	3.00	Mtr	292.00	Mtr	876.00
		40 mm	1.00	point	377.00	each	377.00
33	Pages-E-18, Item no-9 (a)	Supply & Fixing 240 V, 6 A, 3 pin Modular type plug socket (Legrand/L&T) with 6A Modular type switch, without plug top on 4 Module GI Modular type switch board with 3 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc. (For separate Plug)					
34	Page-E/25 Item-5	Distribution wiring in 1.1 KV grade 2x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire (Brand approved by EIC) partly in 20mm size PVC rigid conduit 'FR' (Precision make) [for horizontal run & above false ceiling portion only] and in 19mm bore, 3mm thick polythene pipe [for vertical run embedded in wall], with 1x22/0.3 (1.5 sqmm) single core stranded 'FR' PVC insulated & unsheathed copper wire for ECC, to light/fan/call bell points with Modular type switch (Brand approved by EIC) fixed on Modular GI switch board complete with 2 no. suitable size "Ph & N" copper bar with top cover plate making earthing attachment fixed on wall incl. mending good damages to original finish. [PVC Rigid Conduit only for horizontal run & above false ceiling and vertical run concealed]					
		(b) Average run 6 mtr	2.00	point	929.00	point	1858.00
			2.00	each	377.00	each	754.00
35	Page-E/18 Item-9	(a) Supply & Fixing 240 V, 6 A, 3 pin Modular type plug socket (Brand approved by EIC) with 6A Modular type switch, without plug top on 4 Module GI Modular type switch board with 3 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.					

Sl No	Page & Item	Description of Item	Quantity	Rate	Unit	Amount
36	Page-E/19 Item-14	Supply & Fixing 240 V, 3 nos. 16 A, 3 pin Modular type plug socket with 3 nos. 16A Modular type switch (Brand approved by BIC), 20A Modular switch type SP MCB (C-Curve) and Indicator without plug top on 12 Module GI Modular type switch board with 12 Module top cover plate flushed in wall incl. S&P switch board and cover plate and making necy. connections with PVC Cu wire and earth continuity wire etc.	1.00	each	1458.00	each 1458.00

	68041.57
Add 9% for CGST	6123.74
Add 9% for SGST	6123.74
Total =	80289.05
Add 1% for L.W.Cess	802.89
Grand Total =	81091.94
Say, Rs.	81092.00

RUPES: EIGHTY-ONE THOUSAND NINETY-TWO ONLY.

Kishan
JE-III KPD

Raj
AE-II KPD

TERMS AND CONDITON OF TENDERS

1. All works to be carried out in a manner according to specification for original work now in laid as the regional works in building department circle.
2. All materials, tools, plant and labour, the housing, water supply and transport will have to be provided by Contractor at their own cost inclusive of G.S.T. and other charges.
3. No extra work will be allowed without prior approval.
4. The contractors are requested to inspect the schedule of nature of works at site to save all eventualities connection with works any other information may be obtained from the OC, Buildings Office, Lalbazar. Any place of ignorance after submission of tender by the contractors will not be considered.
5. The quantities as shown against the item of work can be verified according to nature of works. Actual requirement to be done soon after containing the written approval of the Jt. CP(O), but contractors are liable for execution of varied quantities at their accepted rates. The rate of the addition item which are not found in the enclosed schedule will be based on building schedule of the regional works and buildings circle subject to approval of proper authority.
6. The contractors should submit tender enclosed with Trade License, Income Tax return, GST, Credential, Under taking of black listed failure to which will be disqualified.
7. The work will be taken up within 07(Seven) days after receipt of work order, failing to which legal action may be taken against the firm.
8. The Commissioner of Police Kolkata reserves the right to reject any/or all the tender rates without assigning any reason and also to distribute the said works among the tenders . There is no guarantee that the lowest tender will be accepted by the authority concern.
9. Tender addressed to the Commissioner of Police, Kolkata should be sent in a sealed cover super scribed name of tender to be dropped in the sealed TENDER BOX to be kept the OC, Buildings Office, LaLbazar at 18, Lalbazar Street, Kolkata-700 001 within 15.00 hrs on last date.
10. The Tender Committee will open the sealed tender in the Committee Room of Lalbazar, The Agencies may be present or send their authorized representative at the time of opening the sealed tender box.


O.C., Buildings(PHE),
Lalbazar.

PERCENTAGE RATE TENDER AND CONTRACT FOR WORKS: GENERAL RULES
AND DIRECTIONS FOR THE GUIDANCE OF CONTRACTS.

1. All works proposed for execution by contract will be notified in a form of invitation of tender posted in public places and signed by the OC, Buildings Office, Lalbazar.

This form will state the work to be carried out, as well as the date of submitting and opening of tenders and the time allowed for carrying out the work, design and drawings and any other documents required in connection with work signed for the purpose of identification by the OC, Buildings Office, Lalbazar shall also be open for inspection by the contractor at the office of the OC, Building, Lalbazar during office hours.

2. In the event of the quotation being submitted by a firm, it must be signed separately by each member thereof or in the event of the absence of any partner it must be signed on his behalf by a person holding a power of attorney authorizing him to do so. Such power of attorney is to be produced with the tender and same in the case of a firm carried on by one member of a joint family, it must be disclose that the firm is duly registered under the Indian partnership Act.
3. Receipts for payment made on account of work, when executed by a firm, must also be signed by the several partners except where the contractors are described in their tender as a firm in which case the receipts must be signed in the name of the firm by one of the partners or by some other person having authority to give effectual receipts for the firm.
4. Any person who submits a tender shall fill up the usual printed form, stating at what rate he is willing to undertake each item of the work. Tenders which propose any alteration, in the work specified in the said form of invitation of tenders or in the time allowed for carrying out the work, or which contain any other conditions of any sort, will be liable to rejection. No single tender shall include more than one work but contractors who wish to quote for two or more works shall submit a separate tender for each. Tenders shall have the name and number of the work to which they refer written outside the envelope.
5. The Committee will open tenders in the presence of any intending contractors who may present at the time and will enter the amounts of the several tenders in a comparative statement in a suitable form.
6. The accepting authority reserves the right to reject any or all the tender without assigning any reasons and he will not be bound to accept either the lowest tender or any of the tenders.


O.C., Buildings(PHE),
Lalbazar.