

Government of West Bengal  
Office of the Commissioner of Police  
18, Lalbazar Street, Kolkata-700 001.

No. T-375/Gen/24-25

Date – 18.02.2025

NOTICE INVITING TENDER

Sealed tenders in printed form are invited for the following works from eligible tenderers as per particulars given below :

1. Name of work : Repairing and painting of Ladies Changing Room of Muchipara PS at 6, Santosh Mitra Square, Kolkata.  
(Details in ANNEXURE-A)
2. Eligibility : All bonafide contractors /firms having experience / valid license for this type of field.
3. Estimated Cost : **Rs. 97,014/-**
4. Last date for submission of the tender : **27.02. 2025 up to, 15.00 hrs.**
5. Time allowed for completion of works : 10(ten) days after the issue of Work Order.
6. The intending tenderers may inspect the site on any working day during office time.
7. The intending tenderers will have to submit copy of valid Certificate of up to date Clearance of Trade License, Professional Tax, Income Tax, G.S.T and Credential along with tender papers for the work.
8. Sealed Tender addressed to The Commissioner of Police, 18, Lalbazar Street, Kolkata-700001 may be dropped in the box kept in front of the office of the Officer-in-Charge, Building Section, 2<sup>nd</sup> floor, Northern Building, 18, Lalbazar Street, Kolkata-700001 before the last date.
9. Sealed tender may also be sent by Registered Post / Speed Post superscribing the envelope as "~~Spot~~ Tender in response to Tender Notice No. **T-375/Gen/24-25 dt. 18.02. 2025**" so as to reach on or before the last date.



**O.C. Buildings,  
Lalbazar, Kolkata.**

## Annexure-A

For: Repairing and painting of Ladies Changing Room for Muchipara Police Station Building located at 6, Santosh Mitra  
Kata-700012 during year 2024-2025

Sl. No.	Item No.	Description of item	Qty	Rate	Unit	Amount
1	Page-10 Item-1	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m.				
		a) In ground floor including roof.	3.50	cum	447.00	1564.50
2	Page-10 Item-2	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m.				
		In ground floor including roof.				
		(a) upto 150 mm. thick	1.75	cum	939.00	1643.25
3	Page-11 Item-10	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	13.50	sqmtr	19.00	256.50
4	Page-12 Item-13	Removal of rubbish, earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge.	6.50	cum	166.00	1079.00
5	Page-40 Item-27	Cement concrete (1:1.5:3) with graded stone chips, 5.6 mm size with hexagonal square mesh wire netting, I.R.C. fabric mesh or X.P. M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scarping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement including the cost of wire netting, I.R.C or X. P. M. & cost of all handling and scaffolding complete as per direction of Engineer in charge.				
		h) 25 mm thick	2.79	sqmtr	522.00	1456.38
6	Page-41 Item-33	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (6mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes				
		Pakur variety	0.39	cum	5449.00	2125.11
7	Page-45 Item-6	Cleaning the exposed reinforcement preferably upto full diameter by wire brush, applying two coats of polymer based resin removing compound left for 24 hours, removing the coating and then applying two (2) coats of polymer modified anti corrosive protective coating formulated to inhibit the corrosion of reinforcement as per manufacturer's specification]	2.59	sqmtr	782.00	2025.38
8	Page-45 Item-7	Applying epoxy based reactive joining agent for joining the old concrete with fresh concrete to be applied within manufacturer's specified time as per manufacturer's specification (0.4 Kg / m <sup>2</sup> of concrete surface).	4.79	sqmtr	309.00	1480.11
9	Page-45 Item-8	(a) Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification [Cement to be supplied by the Department]	46.50	sqmtr	88.00	4092.00
10	Page-125 Item-14	Supplying, fitting & fixing fibre reinforced polymer (FRP) Composite door shutters as per approved design with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS:4020 door testing performance criteria. In ground floor.				
		(i) 32 mm thick	2.60	sqmtr	2763.00	7183.80
11	Page-115 Item-3	Supplying, fitting and fixing fibre reinforced polymer (FRP) Composite door frame as per approved section with glass fibre reinforced plastic moulded skins and a special sandwich core, so as to impart monolithic composite structure as per approved technology of Department of Science and Technology (DST) to satisfy IS: 4020 door testing performance criteria.				
		(ii) 66mm x 90mm	5.49	mtr	497.00	2728.53
12	Page-140 Item-5	Iron butt hinges of approved quality fitted and fixed with steel screws with ISI mark (viii) 100mm. X 75mm. X 3.50mm.	2.00	each	66.00	132.00



		i) Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with centre bolt and round fitting.					
		(a) 200mm long	2.00	each	134.00	each	268.00
		(i) Door stopper (Brass)	1.00	each	117.00	each	117.00
		j) Hydraulic door closer of approved quality as per I.S.I. standard fitted and fixed complete.					
		(b) Medium (I.S.I. size 2)	1.00	each	1366.00	each	1366.00
		Anodised aluminium barrel / tower / socket bolt (full covered) of approved manufactured from extruded section conforming to I.S. 204/74 fitted and fixed with cadmium plated screws:					
		(iii) 100mm long x 10mm dia. bolt.	2.00	each	53.00	each	106.00
		(vi) 200mm long x 10mm dia. bolt.	2.00	each	78.00	each	156.00
17	Page-155 Item-43	Taking out existing partition/ceiling of particle board, masonite board, ply board, soft-board etc. of any thickness and refixing same in new position with necessary clamps making holes in walls, floor, roof and mending damages if any. (concrete plaster will be paid separately)	42.82	sqmtr	55.00	sqmtr	2355.10
18	Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary. (Ground floor). [Excluding cost of chipping over concrete surface]					
		(ii) With 1:4 cement mortar					
		(a) 20 mm thick plaster	20.52	sqmtr	228.00	sqmtr	4678.56
19	Page-198 Item-4	Removing old scales, blisters etc. of interior surface of walls, ceiling by scraping etc. and preparing smooth and even surface with rendering or cement mortar (1:2) (as necessary) to make the surface suitable for receiving distemper. (Payment against this item will be made only when this has been done on the specific direction of the Engineer-in-charge).	54.58	sqmtr	40.17	sqmtr	555.08
20	Page-198 Item-5	Rendering the Surface of walls and ceiling with White Cement base water proof wall putty of approved make & brand. (1.5 mm thick)	44.50	sqmtr	122.00	sqmtr	5429.00
21	Page-195 Item-7	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor) (a) One Coat (i) Solvent based interior grade Acrylic Primer	93.64	sqmtr	33.70	sqmtr	3155.67
22	Page-196 Item-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats	93.64	sqmtr	70.00	sqmtr	6554.80
23	Page-160 Item-4	Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c ..... in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge. a) False Ceiling (with 4mm thick Pearl Designer Fibre Cement Board and E-Grid T-2430/1510).	43.82	sqmtr	705.00	sqmtr	30893.10

	81400.87
Add 9% C.G.S.T.	7326.08
Add 9% S.G.S.T.	7326.08
+ Total	96053.02
Add 1% L&W Cess	960.53
Grand Total	97013.55
Say Rs	97014.00

(Rupees Ninety Seven Thousand and Forteen Only)

Technically Checked & Verified

by   
Assistant Engineer  
Kolkata Police Directorate  
Govt. of West Bengal

## TERMS AND CONDITON OF TENDERS

1. All works to be carried out in a manner according to specification for original work now in laid as the regional works in building department circle.
2. All materials, tools, plant and labour, the housing, water supply and transport will have to be provided by Contractor at their own cost inclusive of G.S.T. and other charges.
3. No extra work will be allowed without prior approval.
4. The contractors are requested to inspect the schedule of nature of works at site to save all eventualities connection with works any other information may be obtained from the OC, Buildings Office, Lalbazar. Any place of ignorance after submission of tender by the contractors will not be considered.
5. The quantities as shown against the item of work can be verified according to nature of works. Actual requirement to be done soon after containing the written approval of the Jt. CP(O), but contractors are liable for execution of varied quantities at their accepted rates. The rate of the addition item which are not found in the enclosed schedule will be based on building schedule of the regional works and buildings circle subject to approval of proper authority.
6. The contractors should submit tender enclosed with Trade License, Income Tax return, GST, Credential, Under taking of black listed failure to which will be disqualified.
7. The work will be taken up within 07(Seven) days after receipt of work order, failing to which legal action may be taken against the firm.
8. The Commissioner of Police Kolkata reserves the right to reject any/or all the tender rates without assigning any reason and also to distribute the said works among the tenders . There is no guarantee that the lowest tender will be accepted by the authority concern..
9. Tender addressed to the Commissioner of Police, Kolkata should be sent in a sealed cover super scribed name of tender to be dropped in the sealed TENDER BOX to be kept the OC, Buildings Office, Lalbazar at 18, Lalbazar Street, Kolkata-700 001 within 15.00 hrs on last date.
10. The Tender Committee will open the sealed tender in the Committee Room of Lalbazar, The Agencies may be present or send their authorized representative at the time of opening the sealed tender box.



O.C., Buildings,  
Lalbazar.



**PERCENTAGE RATE TENDER AND CONTRACT FOR WORKS: GENERAL RULES**  
**AND DIRECTIONS FOR THE GUIDANCE OF CONTRACTS.**

1. All works proposed for execution by contract will be notified in a form of invitation of tender posted in public places and signed by the OC, Buildings Office, Lalbazar.

This form will state the work to be carried out, as well as the date of submitting and opening of tenders and the time allowed for carrying out the work, design and drawings and any other documents required in connection with work signed for the purpose of identification by the OC, Buildings Office, Lalbazar shall also be open for inspection by the contractor at the office of the OC, Building, Lalbazar during office hours.

2. In the event of the quotation being submitted by a firm, it must be signed separately by each member thereof or in the event of the absence of any partner it must be signed on his behalf by a person holding a power of attorney authorizing him to do so. Such power of attorney is to be produced with the tender and same in the case of a firm carried on by one member of a joint family, it must be disclose that the firm is duly registered under the Indian partnership Act.
3. Receipts for payment made on account of work, when executed by a firm, must also be signed by the several partners except where the contractors are described in their tender as a firm in which case the receipts must be signed in the name of the firm by one of the partners or by some other person having authority to give effectual receipts for the firm.
4. Any person who submits a tender shall fill up the usual printed form, stating at what rate he is willing to undertake each item of the work. Tenders which propose any alteration, in the work specified in the said form of invitation of tenders or in the time allowed for carrying out the work, or which contain any other conditions of any sort, will be liable to rejection. No single tender shall include more than one work but contractors who wish to quote for two or more works shall submit a separate tender for each. Tenders shall have the name and number of the work to which they refer written outside the envelope.
5. The Committee will open tenders in the presence of any intending contractors who may present at the time and will enter the amounts of the several tenders in a comparative statement in a suitable form.
6. The accepting authority reserves the right to reject any or all the tender without assigning any reasons and he will not be bound to accept either the lowest tender or any of the tenders.

  
O.C., Buildings,  
Lalbazar.