

GOVERNMENT OF WEST BENGAL
OFFICE OF THE DEPUTY COMMISSIONER OF POLICE
SOUTHWEST DIVISION (BEHALA)
255/257, D.P.S. ROAD, KOLKATA-33.

NOTICE INVITING QUOTATION


Memo No. SWDI- **459**

Dated- 24.02.2025

Selected quotation in printed forms are invited for the following works from eligible firms as per particulars given below:

1.	Address of site of work & Nature of Work Necessary false ceiling, electrical & minor civil work at IO room of Sarsuna Police Station, 4, Ho Chi Minh Sarani, Sarsuna, Kolkata-700061.	Details of Works Details in Estimate. (Annexure-1)
----	---	--

2. Eligibility of Contractor : All bonafide contractors/firms having experience in similar work.
3. Willing firms have to deposit valid Trade license, P.Tax, PAN, GST Certificate & ITR.
4. Last date of submission of the quotation: At 15.00 hrs. on 03.03.2025
5. Quotation duly sealed should be deposited at the drop box physically which is kept in front of DRO, SWD (Behala) on or before 03.03.2025 by 15.00 hrs. and the same to be opened in presence of the Tender committee & willing quotationer.
6. The quotation will be opened on 04.03.2025 at 12.00 hrs. at DC, SWD Office, 255/257, D.P.S. Road, Kolkata-33.
7. Time allowed for completion of work : 08 (Eight) days after the issuance of work order.
8. The intending firms should inspect the site before submitting the quotation on any working day during office hours for details of the work. They may contact with Building Maintenance Officer SWD before visiting the site.
9. Sealed quotation addressed to Deputy Commissioner of Police, South West Division (Behala), Kolkata, 255/257, D.P.S. Road, Kolkata-700033 and should be dropped in the box kept in front of DC, SWD Office or sealed quotation may be sent by Registered Post/Speed Post super scribing the envelope as "Quotation in response to Memo No. SWDI- **459**..... Dt- **24.02.25** so as to reach on or before the last date mentioned above.
10. Work will be started by 03(three) days after issuance of work order.
11. The work should be done as per specification attached in Annexure-I with the total satisfaction of the authority.
12. The Authority reserves the right to reject any Quotation without assigning any reason in this regard.
13. For any other information contact with ASI Pijush Kanti Dev (Mobile No. 9123922700) of SWD.

 **24.02.25**
Deputy Commissioner of Police
South West Division (Behala)
Deputy Commissioner of Police
South West Division (Behala), Kolkata

ESTIMATE

Works:-Necessary false ceiling, electrical & minor civil work at IO room of Sarsuna Police Station, 4, Ho Chi Minh Sarani, Sarsuna, Kolkata - 700061.

S. No.	Location	Description of Item	Qty	Unit	Rate	Amount
1	Page-92 Item-1	Taking out old damaged tarfelt from the roof, parapet etc. preparing the roof surfaces by removing all spoils, blisters, moss etc. from the working site and disposal of the same beyond the compound and cleaning the site in all respect as per direction of Engineer-in-Charge.	26.10	sqmtr	12.00	313.20
2	R.M.	P/F TARFELT ISI MAKE	26.10	sqmtr	325.00	8482.50
3	PWD EL / SCHEDULE	Supply & delivery of EPC make 9" Sweep AC Exhaust fan	1.00	each	2950.00	2950.00
4	R.M.	Crompton High Flo Wave Plus 400 mm 3 Blade Wall Fan	3.00	each	2956.00	8868.00
5	Page-114 Item-1	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected upto three decimals). (e) Sal : Malaysian	0.04	cum	98112.00	3924.48
6	Page-160 Item-4	Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 4 mm thick High Pressure Steam Cured Non Asbestos Fibre Cement Standard Ceiling Board (Density > 1500 Kg/m3) of size 595 mm X 595 mm, conforming IS 14862 & Type A Category IV of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-In-charge.a) False	21.30	sqmtr	705.00	15016.50
7	Page-11 Item-10	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	14.08	sqmtr	19.00	267.52
8	Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (iii) With 1:6 cement mortar (c) 15 mm thick plaster	14.08	sqmtr	151.00	2126.08
9	Page-204 Item-5	(b) Rendering the surface of walls and ceiling with white cement based wall putty of approved make and brand(1.5mm thick)	14.08	sqmtr	110.00	1548.80
10	Page-200 Item-1	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	76.52	sqmtr	38.00	2907.76
11	Page-196 Item-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats	25.78	sqmtr	70.00	1804.60
12	Page-200 Item-2	(a) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : On timber or plastered surface : (iv) Two coats (with any shade except white)	50.74	sqmtr	81.00	4109.94
13	PWD EL / SCHEDULE	Supplying and fixing double-door SPN MCB Distribution Board with IP-42/43 protection, concealed in wall after cutting the wall & mending good the damages to original finish incl. Inter connection with suitable size of copper wire and neutral link & provision for earthing attachment 2+16 way Enclosure (607713)	1.00	Each	2200.00	2200.00
14	Page-E/14 Item-2	Distribution wiring in 1.1KV grade 2x22/0.3(1.5sqmm) single core stranded 'FR'PVC insulated & unsheathed copper wire....(b) Average run 6mtr	3.00	points	795.00	2385.00
15	Page-E/15 Item-4	Distribution Wiring in 1.1KV grade 2x22/0.3(1.5sqmm) single core stranded 'FR'PVC insulated & unsheathed copper wire....(a) on board	2.00	points	77.00	154.00
16	M.R.	SITC OF 20 W / 22 W LED, CIR REC ,5700K	18.00	each	792.54	14265.72

Location	Description of item	Qty	Unit	Rate	Amount
PWD EL / SCHEDULE	S&F of 1x1200 mm LED tube(Make:- (Philips-Mas LED tube 1200mm 18W865 T8 - 2100lm/ Similar Crompton/Similar Havels) including necessary fittings, Switch & wiring.	1.00	each	650.00	650.00
18 Page-E/14 Item-1a	Distribution wiring in 1.1 KVsingle core stranded 'FR'PVC insulated & unsheathed copper wire (i) 2x22/0.3(1.5sqmm)+1 x22/0.3(1.5sqmm)ECC (from SPN DB to SB)	86.36	mtr	117.30	10130.03
19 Page-E/6 Item-21	Supply & Fixing 240 V 20 A plug socket with separate 20A Piano key type switch(Brand approved by EIC) on existing metal with switchboard embeded in wall....	1.00	each	260.00	260.00
20 Page-E/6 Item-22	Supply & Fixing 240 V 6 A plug socket with separate 6A Piano key type switch(Brand approved by EIC)....	3.00	each	373.00	1119.00
Taxable Value					78898.13
Add 9% for CGST					7100.83
Add 9% for SGST					7100.83
Total with Tax					93099.79
Add 1% LW Cess					931.00
Final Total					94030.79
R/O (+)					0.21
SAY					94031.00

Rupees in words: Ninty Nine Thousand Five Hundred Eighty Three And Zero Paise Only

Ninty Four Thousand Thirty one only.

[Signature]
AE KPD

Technically Checked & Verified

[Signature]
Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal
18/02/25