

GOVERNMENT OF WEST BENGAL
OFFICE OF THE DEPUTY COMMISSIONER OF POLICE
SOUTHWEST DIVISION (BEHALA)
255/257, D.P.S. ROAD, KOLKATA-33.

NOTICE INVITING QUOTATION

Memo No. SWDI- 950

Dated- 29.04.2025

Selected quotation in printed forms are invited for the following works from eligible firms as per particulars given below:

1.	<table><tr><th>Address of site of work & Nature of Work</th><th>Details of Works</th></tr><tr><td>Necessary Civil works including Tiles, Brick, Shed and Painting at Mess within Parnashree Police Station, Upen Banerjee Road, Block-14, Parnashree Pally, Kolkata-700060.</td><td>Details in Estimate. (Annexure-1)</td></tr></table>	Address of site of work & Nature of Work	Details of Works	Necessary Civil works including Tiles, Brick, Shed and Painting at Mess within Parnashree Police Station, Upen Banerjee Road, Block-14, Parnashree Pally, Kolkata-700060.	Details in Estimate. (Annexure-1)
Address of site of work & Nature of Work	Details of Works				
Necessary Civil works including Tiles, Brick, Shed and Painting at Mess within Parnashree Police Station, Upen Banerjee Road, Block-14, Parnashree Pally, Kolkata-700060.	Details in Estimate. (Annexure-1)				

2. Eligibility of Contractor : All bonafide contractors/firms having experience in similar work.
3. Willing firms have to deposit valid Trade license, P.Tax, PAN, GST Certificate & ITR.
4. Last date of submission of the quotation: At 15.00 hrs. on 06.05.2025
5. Quotation duly sealed should be deposited at the drop box physically which is kept in front of DRO, SWD (Behala) on or before 06.05.2025 by 15.00 hrs. and the same to be opened in presence of the Tender committee & willing quotationer.
6. The quotation will be opened on 07.05.2025 at 12.00 hrs. at DC, SWD Office, 255/257, D.P.S. Road, Kolkata-33.
7. Time allowed for completion of work : 08 (Eight) days after the issuance of work order.
8. The intending firms should inspect the site before submitting the quotation on any working day during office hours for details of the work. They may contact with Building Maintenance Officer SWD before visiting the site.
9. Sealed quotation addressed to Deputy Commissioner of Police, South West Division (Behala), Kolkata, 255/257, D.P.S. Road, Kolkata-700033 and should be dropped in the box kept in front of DC, SWD Office or sealed quotation may be sent by Registered Post/Speed Post super scribing the envelope as "Quotation in response to Memo No. SWDI-250 Dt- 29.04.2025" so as to reach on or before the last date mentioned above.
10. Work will be started by 03(three) days after issuance of work order.
11. The work should be done as per specification attached in Annexure-I with the total satisfaction of the authority.
12. The Authority reserves the right to reject any Quotation without assigning any reason in this regard.
13. For any other information contact with ASI Pijush Kanti Dev (Mobile No. 9123922700) of SWD.

29.04.2025
Deputy Commissioner of Police
South West Division (Behala)
Deputy Commissioner of Police
South West Division (Behala), Kolkata

ESTIMATE

Work: Necessary Civil works including Tiles, Brick, Shed and Painting at Mess within Parnashree Police Station, Upen Road, Block-14, Parnashree Pally, Kolkata-700060

Page & Item No	Description of item	Quantity		Rate	Unit	Amount
1	Page-64 Item-35	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc.				
	(A) Floor With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (i) Coloured decorative	35.05	sqmtr	755.00	sqmtr	26459.92
	(B) Wall With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (a) Area of each tile upto 0.09 Sq.m (i) Coloured decorative	5.94	sqmtr	757.00	sqmtr	4496.58
2	Page-16 Item-17	125 mm. thick brick work with 1st class bricks in cement mortar (1:3) in ground floor.		8.54	sqmtr	765.00
3	Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] ii) with 1:4 cement mortar. (b) 10mm thk plaster		17.08	sqmtr	133.00
4	Page-99 Item-1	M.S. structural works in columns, beams etc. with simple rolled structural members (e.g. joists, angle, channel sections conforming to IS: 226, IS: 808 & SP (6)- 1964 connected to one another with bracket, gussets, cleats as per design, direction of Engineer-in- charge complete including cutting to requisite shape and length, fabrication with necessary bolting, metal arc welding conforming to IS: 816- 1956 & IS: 1995 using electrodes of approved make and brand conforming to IS:814- 1957, haulage, hoisting and erection all complete. The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental charges such as electricity charges, labour insurance charges etc.....) For structural members of specified sections weighing not less than 22.5 Kg./m		0.06	M.T.	59119.00
					M.T.	3547.14

3
-15

		Supplying, fitting and fixing Black Stone slab used in Kitchen slab, alcove, wardrobe etc. laid and jointed with necessary adhesive Cement mortar (1:2) including grinding or polishing as per direction of Engineer-in -Charge in Ground Floor.(b) Slab Thickness above 25 mm and upto 37.5 mm	2.24	sqmtr	712.00	sqmtr	1594.88
6	Page-100 Item-2	M.S. structural works in roof trusses with tubular sections conforming to IS: 806-1957 & IS: 1161- 1958 connected to one another with bracket, gusset cleats as per design, direction of Engineer-in-charge complete including cutting to requisite size, fabrication with necessary metal arc welding conforming to IS: 816- 1956 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 1957, haulage, hoisting and erection all complete. The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental chages such as electricity charges, labour insurance charges etc. (i) For trusses spanning up to 12.00 m	0.20	M.T.	72951.00	M.T.	14590.20
7	Page-81 Item-9	Galvanised corrugated iron sheet work (excluding the supporting frame work) fitted and fixed with 10 mm. dia J or L hook-bolts, limpet and bitumen washers and putty complete with 150 mm. end lap and one corrugation minimum side lap. (Payment to be made on area of finished work)(GCI sheet to be supplied by contractor) a) With 0.60 mm thick sheet	14.85	sqmtr	619.00	sqmtr	9192.15
8	Page-204 Item-5	(b) Rendering the surface of walls and ceiling with white cement based wall putty of approved make and brand(1.5mm thick)	29.99	sqmtr	110.00	sqmtr	3299.14
9	Page-200 Item-1	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	99.97	sqmtr	38.00	sqmtr	3799.01
10	Page-196 Item-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats	99.97	sqmtr	70.00	sqmtr	6998.18
Total							82781.94
Add 9% for CGST							7450.37
Add 9% for SGST							7450.37
Total Incl. GST							97682.69
Add 1% for L.W.Cess							976.83
Grand Total							98659.52
Say							98660.00

RUPEES: NINETY-EIGHT THOUSAND SIX HUNDRED SIXTY ONLY.

Technically Checked & Verified
by
Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal