

**GOVERNMENT OF WEST BENGAL**  
**OFFICE OF THE DEPUTY COMMISSIONER OF POLICE**  
**SOUTHWEST DIVISION (BEHALA)**  
**255/257, D.P.S. ROAD, KOLKATA-33.**

**NOTICE INVITING QUOTATION**


Memo No. SWDI- 1125

Dated- 19.05.2025

Selected quotation in printed forms are invited for the following works from eligible firms as per particulars given below:

1.	<table><tr><th>Address of site of work &amp; Nature of Work</th><th>Details of Works</th></tr><tr><td>Necessary replacement of damage false ceiling and allied works of 1<sup>st</sup> floor police barrack at Sahapur out post under Behala PS 10, B.L. Saha Road, Kolkata-700053</td><td>Details in Estimate. (Annexure-1)</td></tr></table>	Address of site of work & Nature of Work	Details of Works	Necessary replacement of damage false ceiling and allied works of 1 <sup>st</sup> floor police barrack at Sahapur out post under Behala PS 10, B.L. Saha Road, Kolkata-700053	Details in Estimate. (Annexure-1)
Address of site of work & Nature of Work	Details of Works				
Necessary replacement of damage false ceiling and allied works of 1 <sup>st</sup> floor police barrack at Sahapur out post under Behala PS 10, B.L. Saha Road, Kolkata-700053	Details in Estimate. (Annexure-1)				

2. Eligibility of Contractor : All bonafide contractors/firms having experience in similar work.
3. Willing firms have to deposit valid Trade license, P.Tax, PAN, GST Certificate & ITR.
4. Last date of submission of the quotation: At 15.00 hrs. on 26.05.2025
5. Quotation duly sealed should be deposited at the drop box physically which is kept in front of DRO, SWD (Behala) on or before 26.05.2025 by 15.00 hrs. and the same to be opened in presence of the Tender committee & willing quotationer.
6. The quotation will be opened on 27.05.2025 at 12.00 hrs. at DC, SWD Office, 255/257, D.P.S. Road, Kolkata-33.
7. Time allowed for completion of work : 08 (Eight) days after the issuance of work order.
8. The intending firms should inspect the site before submitting the quotation on any working day during office hours for details of the work. They may contact with Building Maintenance Officer SWD before visiting the site.
9. Sealed quotation addressed to Deputy Commissioner of Police, South West Division (Behala), Kolkata, 255/257, D.P.S. Road, Kolkata-700033 and should be dropped in the box kept in front of DC, SWD Office or sealed quotation may be sent by Registered Post/Speed Post super scribing the envelope as "Quotation in response to Memo No. SWDI- 1125 Dt- 19.05.2025 so as to reach on or before the last date mentioned above.
10. Work will be started by 03(three) days after issuance of work order.
11. The work should be done as per specification attached in Annexure-I with the total satisfaction of the authority.
12. The Authority reserves the right to reject any Quotation without assigning any reason in this regard.
13. For any other information contact with ASI Pijush Kanti Dev (Mobile No. 9123922700) of SWD.

  
Deputy Commissioner of Police  
South West Division (Behala)  
**Deputy Commissioner of Police**  
**South West Division (Behala), Kolkata**



# ESTIMATE

Name of Work :-

Necessary replacement of damage false ceiling and allied works of 1st floor police barrack at sahapur out post under Behala PS 10, B.L.Saha Road,Kolkata-700053

SL.NO.	Page No. & Item No.	Description of Item	Quantity	Unit	Rate (Rs.)	Amount
1	Page-13 Item-17	Dismantling carefully wooden walling, flooring of ceiling and stacking dismantled materials as directed.	93.82	sqmtr	14.00	1313.48
2	Page- 200, Item No. -01	(a) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	59.21	sqmtr	38.00	2249.98
3	Page- 200, Item No. -02	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary.(a) On timber or plastered surface :With super gloss (hi-gloss) -(iv) Two coats (with any shade except white)	59.21	sqmtr	81.00	4796.01
4	Page-165 Item-17	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special section,power presed from M.S.Sheet and galvanised with zinc. Coating of 150gms/sqmtr(both side inclusive) as per IS:277 and consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 27mm and 37mm,at 1200 mm centre to centre,one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50 mm long with 6mm dia bolt,other flange of cleat fixed to the angle hangers of 25 x 10 x 0.50mm of required length with nuts & bolts of required size and other end of angle henger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200mm centre to centre,to which the ceiling section 0.5mm thick bottom wedge of 80mm with tapered flanges of 26mm each havings lips of 10.5mm,at 450mm centre to centre,shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64mm dia x 230mm long G.I.wire at every junction,including fixing perimeter channels 0.5 mm thick 27mm high having flanges of 20mm and 30mm long,the perimeter of ceiling fixed to wall / partition with the help of rawl at 450mm centre, with 25mm long dry wall screws @ 230mm interval,including fixing of Gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230mm c/c,including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound,jointing tapes,finishing with jointing compound in 3 layers covering upto 150mm on both sides of joint and two coats of primer suitable for board,all as per manufacture's specification and also including the cost of making openings for light fittings,grill,diffusers,cutouts made with frame of perimeter channels suitable fixed,all complete as per drawings,specification and direction of the Engineer-in-Charge but excluding the cost of painting with(ISI Mark on Board)	63.87	sqmtr	1157.00	73897.59
SUB TOTAL						82257.06
ADD. C.G.S.T. 9%						7403.14
ADD. S.G.S.T. 9%						7403.14
TOTAL						97063.33
ADD. L.W.C. 1%						970.63
GRAND TOTAL						98033.96
Amount (In word):- Rupees Ninety Eight Thousand Thirty Four Only						Say Rs. 98034

Technically Checked & Verified

by  
22/04/25  
Assistant Engineer  
Kolkata Police Directorate  
of West Bengal