

**GOVERNMENT OF WEST BENGAL
OFFICE OF THE DEPUTY COMMISSIONER OF POLICE
SOUTH WEST DIVISION (BEHALA)
255/257, D.P.S. ROAD, KOLKATA-33.**

NOTICE INVITING QUOTATION

Memo No. SWDI- 582

Dated- 06/03/26

Selected quotation in printed forms are invited for the following works from eligible firms as per particulars given below:

Address of site of work & Nature of Work	Details of Works
Necessary repairing and painting with allied works of process room, construction of ramp, collapsible gate at Behala PS, 131, D.H.Road, kol-700034.	Details in Estimate. (Annexure-1)

1. Eligibility of Contractor : All bonafide contractors/firms having experience in similar work.
2. Willing firms have to deposit valid Trade license, P.Tax, PAN, GST Certificate & ITR.
3. Last date of submission of the quotation: At 15.00 hrs. on 13.03.2026
4. Quotation duly sealed should be deposited at the drop box physically which is kept in front of DRO, SWD (Behala) on or before 13.03.2026 by 15.00 hrs. and the same to be opened in presence of the Tender committee & willing quotationer.
5. The quotation will be opened on 16.03.2026 at 12.00 hrs. at DC, SWD Office, 255/257, D.P.S. Road, Kolkata-33.
6. Time allowed for completion of work : 08 (Eight) days after the issuance of work order.
7. The intending firms should inspect the site before submitting the quotation on any working day during office hours for details of the work. They may contact with Building Maintenance Officer SWD before visiting the site.
8. Sealed quotation addressed to Deputy Commissioner of Police, South West Division (Behala), Kolkata, 255/257, D.P.S. Road, Kolkata-700033 and should be dropped in the box kept in front of DC, SWD Office or sealed quotation may be sent by Registered Post/Speed Post super scribing the envelope as "Quotation in response to Memo No. SWDI- 582 Dt- 06/03/26 so as to reach on or before the last date mentioned above.
9. Work will be started by 03(three) days after issuance of work order.
10. The work should be done as per specification attached in Annexure-I with the total satisfaction of the authority.
11. The Authority reserves the right to reject any Quotation without assigning any reason in this regard.
12. For any other information contact with ASI Mustaqul Hoque (Mobile No. 7003233740) of SWD.

Sd/-

Deputy Commissioner of Police
South West Division (Behala)

ESTIMATE


Name of Work :-

Repairing and painting with allied works of Process Room, Construction of Ramp and installation of Collapsible gate in front of proposed SERESTA at ground floor of Behala Police Station During the F/Y 2025-26.

SL.NO.	Page No. & Item No.	Description of Item	Quantity	Unit	Rate (Rs.)	Amount
1	page-10, Item-01	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof.	1.28	cum	447.00	572.16
2	Page - 214, Item No.- 02	Strong bamboo posts, posts plates, rafters, ties etc. fitted and fixed complete with coil rope or nails as directed. (Embedded portion of posts shall also be paid for against this item cost of digging hole and repacking being paid for separately): (a) 75 mm. dia bamboo	36.00	mtr	50.00	1800.00
3	Page - 11, Item No.- 10	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	10.03	sqmtr	19.00	190.57
4	Page - 45, Item No.- 08	Applying 2 coats of bonding agent with synthetic multi functional rubber emulsion having adhesive and water proofing properties by mixing with water in proportion (1 bonding agent : 4 water : 6 cement) as per Manufacturer's specification [Cement to be supplied by the Department]	10.03	sqmtr	88.00	882.64
5	Page - 45, Item No.- 06	Cleaning the exposed reinforcement preferably upto full diameter by wire brush, applying two coats of polymer based rust removing compound left for 24 hours, removing the coating and then applying two (2) coats of polymer modified anti corrosive protective coating formulated to inhibit the corrosion of reinforcement as per manufacturer's specification][Mode of measurement: The affected surface area of reinforcement shall be considered for payment]	0.80	sqmtr	782.00	625.60
6	Page - 45, Item No.- 07	Applying epoxy based reactive joining agent for joining the old concrete with fresh concrete to be applied within manufacturer's specified time as per manufacturers specification. (0.4 Kg / m ² of concrete surface).	0.80	sqmtr	309.00	247.20
7	Page - 40, Item No.- 27	Cement concrete (1:1.5:3) with graded stone chips 5.6 mm size with hexagonal square mesh wire netting, I.R.C. fabric mesh or X.P. M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scarping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement including the cost of wire netting I.R.C or X. P. M. & cost of all handling and scaffolding complete as per direction of Engineer-in -charge. a) 20 mm thick	0.80	sqmtr	491.00	392.80
8	Page-77 Item-9	Taking out Mirzapur or glazed porcelain tiles carefully by chiselling from walls or floor including stacking serviceable material as directed.	9.00	sqmtr	106.00	954.00
9	Page- 64 Item- 35	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. (B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m (b) Area of each tile above 0.09 Sq.m (i) Coloured decorative	15.00	sqmtr	1109.00	16635.00
10	page-189, Item-1-(ii)- b	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (b) 15 mm thick plaster Ground floor	10.03	sqmtr	167.00	1675.01
11	Page-198 Item-4	Removing old scales, blisters etc. of interior surface of walls, ceiling by scraping etc. and preparing smooth and even surface with rendering or cement mortar (1:2) (as necessary), to make the surface suitable for receiving distemper. (Payment against this item will be made only when this has been done on the specific direction of the Engineer-in-charge).	82.46	sqmtr	10.17	838.62
12	Page-198 Item-5	Rendering the Surface of walls and ceiling with White Cement base water proof wall putty of approved make & brand.(1.5 mm thick)	92.49	sqmtr	122.00	11283.78
13	Page-195 Item-7	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor) i) Water based interior grade Acrylic Primer	92.49	sqmtr	30.80	2848.69
14	Page-201 Item-04	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) : (Two coats) ii) Luxury Quality	92.49	sqmtr	70.00	6474.30

Continue ...page 2

	Page- 200, Item No. -01	(a) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	3.90	sqmtr	38.00	148.20
16	Page- 200, Item No. -01	(b) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	7.52	sqmtr	29.00	218.08
17	Page- 200, Item No. -02	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary.(a) On timber or plastered surface :With super gloss (hi-gloss) -(iv) Two coats (with any shade except white)	3.90	sqmtr	81.00	315.90
18	Page- 200, Item No. -02	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary. (b) On steel or other metal surface(iv) Two coats (with any shade except white)	7.52	sqmtr	79.00	594.08
19	Page-106 Item-18	Collapsible gate with 40mm x 40mm x 6mm Tee as top and bottom guide rail, 20mm x 10mm x 2mm vertical channels 100mm apart in fully stretched position 20mm x 5mm M.S. flats as collapsible bracings properly rivetted and washered Including 38mm steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc. in walls, floors etc. and making good damages complete. In ground floor.	3.76	sqmtr	3402.00	12791.52
		(A) Extra over the corresponding item of collapsible gate for top hung	3.76	sqmtr	148.00	556.48
20		supplying and fixing of glow sign board made of polycarbonate front sheet with pasting the letter by Vinyl sheet (colour approved by authority) with supply and fixing of 600mm LED tube fittings in the glow sign box.The box will be fabricated with aluminium channel structure including covered the box all side(except front) by GI sheet with provision for fixing on existing structure as per direction of E.I.C	26.00	sqft	675.00	17550.00
21	Page-D/18 Item-9 (a)	Supply & Fixing 240 V, 6 A. 3 pin Modular type plug socket (Legrand/L&T/Panasonic/Honeywell) with 2nos. 6A Modular type switch, without plug top on 4 Module GI Modular type switch board with 3 Module top cover plate flushed in wall incl. S&F switch board and cover plate and making necy, connections with PVC Cu wire and earth continuity wire etc. (For seperate plug)	2.00	point	433.00	866.00
22	Page-E/14 Item-1	(a) Distribution wiring in 1.1 KV single core stranded 'FR PVC insulated & unsheathed copper wire (Brand approved by EIC) in 20mm size PVC rigid conduit 'FR'(Precision make) incl. necy, fittings as required. (i) 2 x 22/0.3 (1.5 sqmm)+ 1 x 22/0.3 (1.5 sqmm) ECC	22.00	mtr	116.00	2552.00
23	PWD EL/ SCHEDULE	Supply of skilled Labour (Memo No.49/stat/14/RW/24/2023/LCS/ILC dated 12/12/2023)	4.00	each	503.80	2015.20
SUB TOTAL					₹ 83,027.83	
ADD.G.S.T. 18%					₹ 14,945.01	
TOTAL AMOUNT					₹ 97,972.84	
ADD. L.W.C. 1%					₹ 979.73	
GRAND TOTAL					₹ 98,952.57	
Say Rs.					₹ 98,953.00	
Amount (In word):- Rupees Ninety Eight Thousand Nine Hundred and Fifty Three Only.						

Technically Checked & Verified
by

25/02/2026
Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal