

Government of West Bengal
Office of the Commissioner of Police
18, Lalbazar Street, Kolkata-700 001.

No. T-083/Gen/26-27

Date – 08. 07. 2026

NOTICE INVITING TENDER

Sealed tenders in printed form are invited for the following works from eligible tenderers as per particulars given below :

1. Name of work : Necessary replacement of the sewerage line with allied works inside the Jorabagan PS Lock Up at 74, Nimtala Ghat Street, Kolkata.
(Details Estimate annexed)
2. Eligibility : All bonafide contractors /firms having experience / valid license for this type of field.
3. Estimated Cost : Rs. 57,823/-
4. Last date for submission of the tender : 17. 07. 2026 up to 15.00 hrs.
5. Time allowed for completion of works : 07(seven) days after the issue of Work Order.
6. The intending tenderer may inspect the site on any working day during office time.
7. The intending tenderers will have to submit copy of valid Certificate of up to date Clearance of Trade License, Professional Tax, Income Tax, G.S.T and Credential along with tender papers for the work and tenderers must quote percentage rate of tender in the annexed estimate .
8. Sealed Tender addressed to The Commissioner of Police, 18, Lalbazar Street, Kolkata-700001 may be dropped in the box kept in front of the office of the Officer-in-Charge, Building Section, 2nd floor, Northern Building and also in the Drop Box kept beside In Gate, Lalbazar at 18, Lalbazar Street, Kolkata-700001 before the last date.
9. Sealed tender may also be sent by Registered Post / Speed Post superscribing the envelope as "Tender in response to Tender Notice No. T-083/Gen/26-27 dt. 08.07. 2026" so as to reach this office on or before the last date & time.


O.C. Buildings,
Lalbazar, Kolkata.

Estimate

316

work: Necessary replacement of the sewerage line with allied works inside the Jorabagan Police Station Lockup
located at 74, Nimtola Ghat Street, Kolkata-700006 during the year 2026-2027

Page & Item No	Description of item	Qty		Rate	Unit	Amount
Page-11 Item-10	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	20.24	sqmtr	19.00	sqmtr	384.56
2 Page-45 Item-5	Cleaning the concrete surface by removing dirt and debris, marking defective locations and removing loose concrete by careful stripping untill hard surface is exposed, cutting the concrete to regular shape, wire brushing the exposed surface and removing debris from site complete as per direction of the Engineer - in - Charge.	12.32	sqmtr	90.00	sqmtr	1108.80
3 Page-45 Item-6	Cleaning the exposed reinforcement preferably upto full diameter by wire brush, applying two coats of polymer based rust removing compound left for 24 hours, removing the coating and then applying two (2) coats of polymer modified anti corrosive protective coating formulated to inhibit the corrosion of reinforcement as per manufacturer's specification]	0.20	sqmtr	782.00	sqmtr	156.40
4 Page-189 Item-1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including round off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface].					
	(i) With 1:6 cement mortar. (b) 20 mm thick plaster	14.36	sqmtr	175.00	sqmtr	2513.00
	(ii) With 1:4 cement mortar.(c) 10 mm thick plaster	6.58	sqmtr	133.00	sqmtr	875.14
5 Page-40 Item-27	Cement concrete (1:1.5:3) with graded stone chips 5.6 mm size with hexagonal square mesh wire netting, I.R.C. fabric mesh or X.P. M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scarping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement including the cost of wire netting I.R.C or X. P. M. & cost of all handling and scaffolding complete as per direction of Engineer-in-charge.					
	b) 25 mm thick	5.00	sqmtr	517.00	sqmtr	2585.00
6 Page-12 Item-13	Removal of rubbish,earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge.	2.00	cum	166.00	cum	332.00
7 Page- 68 Item-23 (S & P)	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992					
	(A) (i) Single Socketed 3 Meter Length. (b)110 mm	5.00	mtr	292.00	mtr	1460.00
	(B) Fittings					
	(x) Bend 87.5° . (b)110 mm	2.00	each	120.00	each	240.00
	xiv) Cross Tee with Door. (b)110 mm	2.00	each	239.00	each	478.00
	(I) Rubber Ring.(b)110 mm	2.00	each	17.00	each	34.00
	(xIvi) Door Cap. (b)110 mm	2.00	each	51.00	each	102.00
	(C) Rubber Lubricant 500 ML	0.50	500 ML	187.00	500 ML	93.50
	(D) Solvent Cement 250 ML	0.25	250 ML	103.00	250 ML	25.75
8 Page- 99 Item-23 (S & P)	Dismantling and refixing drain pipe including cutting trench and refilling the same.(i) Upto 100 mm	5.34	mtr	70.00	mtr	373.80
9 Page- 68 Item-24 (S & P)	Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in walls or R.C. floor where necessary and mending good all damages excluding the cost of masonry or concrete work, if necessary, but including the cost and fitting and fixing holder bat clamps (any floor) or for underground work including cutting trenches upto 1.5 metre and refilling the same complete as per direction of the Engineer-in-charge. (Payment will be made on centre line measurement of the total pipeline including specials.					
	(A)Above ground.(ii) 110 mm dia.	5.00	mtr	57.00	mtr	285.00
10 Page- 65 Item-16 (S & P)	Supplying, fitting and fixing with cement jointing (3:1) salt glazed stoneware pipe including excavation of earth upto 1.50 metre depth in all sorts of soil both mixed or unmixed and refilling (but excluding concreting at bottom and sides).					
	(ii) 225 mm	15.00	mtr	528.00	mtr	7920.00
11 Page-14 Item-1	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	7.00	sqmtr	358.00	sqmtr	2506.00

		ement concrete with graded jhama khoa (30 mm size) excluding shuttering. In ground floor and foundation. (a) 1:3:6 proportion	1.50	cum	4572.00	cum	6858.00
		Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc.					
		(A) Floor					
		With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m.					
		(a) Area of each tile above 0.09 Sq.m	4.22	sqmtr	910.00	sqmtr	3840.20
		(i) Coloured decorative					
		(B) Wall					
		With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m.					
		(a) Area of each tile above 0.09 Sq.m	2.64	sqmtr	1102.00	sqmtr	2909.28
		(i) Coloured decorative					
14	Page- 79 Item-3 (S & P)	Supplying, fitting and fixing Anglo-Indian W.C. in white glazed vitreous china ware of approved make complete in position with necessary bolts, nuts etc.					
		(a) With 'P' trap (with vent)	1.00	each	3104.00	each	3104.00
15	Page- 87 Item-1 (S & P)	Constructing Inspection pit of inside measurement 600mm X 600mm X upto 600mm (depth) with 250 mm thick 1st. class brick work in cement mortar (1:4) on all sides, bottom of the pit consisting of 100 mm thick cement concrete (1:3:6) with stone chips over a layer of jhama brick flat soling, 15 mm thick (1:4) cement plaster to inside walls and out-side walls upto G.L. and 20 mm. thick (1:4) plaster to bottom of the pit, providing necessary invert with cement concrete (1:3:6) with stone chips as per direction, neat cement finishing to entire internal surfaces, top of the pit covered with 100 mm thick R.C.C. slab (1:1.5:3) with stone chips and necessary reinforcements upto 1% and shuttering including 6 mm thick cement plaster (1:4) in all external surfaces of the slab and one 560 mm dia. R.C.C. manhole cover of approved make supplied, fitted and fixed in the slab with necessary fittings, necessary earthwork in excavation in all sorts of soil, filling sides of the pit with earth and removing spoils after work complete in all respect with all costs of labour and materials.					
		i) With Pakur variety. (SAIL /TATA/RINL)	1.00	no	7303.00	no	7303.00
		(iii) Extra for each additional depth of 150 mm or part thereof beyond initial 600mm depth.	2.00	no	1515.00	no	3030.00
							48517.43
					Add 9% for C.G.S.T.		4366.57
					Add 9% for S.G.S.T.		4366.57
					Total		57250.57
					Add 1% for L.W.Cess		572.51
					Grand Total		57823.07
					Say Rs		57823.00

(Rupees Fifty Seven Thousand Eight Hundred and Twenty Three Only)

Technically Checked & Verified

by
30/12/2016
Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal

TERMS AND CONDITON OF TENDERS

1. All works to be carried out in a manner according to specification for original work now in laid as the regional works in building department circle.
2. All materials, tools, plant and labour, the housing, water supply and transport will have to be provided by Contractor at their own cost inclusive of G.S.T. and other charges.
3. No extra work will be allowed without prior approval.
4. The contractors are requested to inspect the schedule of nature of works at site to save all eventualities connection with works any other information may be obtained from the OC, Buildings Office, Lalbazar. Any place of ignorance after submission of tender by the contractors will not be considered.
5. The quantities as shown against the item of work can be verified according to nature of works. Actual requirement to be done soon after containing the written approval of the Jt. CP(O), but contractors are liable for execution of varied quantities at their accepted rates. The rate of the addition item which are not found in the enclosed schedule will be based on building schedule of the regional works and buildings circle subject to approval of proper authority.
6. The contractors should submit tender enclosed with Trade License, Income Tax return, GST, Credential, Under taking of black listed failure to which will be disqualified.
7. The work will be taken up within 07(Seven) days after receipt of work order, failing to which legal action may be taken against the firm.
8. The Commissioner of Police Kolkata reserves the right to reject any/or all the tender rates without assigning any reason and also to distribute the said works among the tenders . There is no guarantee that the lowest tender will be accepted by the authority concern..
9. Tender addressed to the Commissioner of Police, Kolkata should be sent in a sealed cover super scribed name of tender to be dropped in the sealed TENDER BOX to be kept the OC, Buildings Office, Lalbazar at 18, Lalbazar Street, Kolkata-700 001 within 15.00 hrs on last date.
10. The Tender Committee will open the sealed tender in the Committee Room of Lalbazar, The Agencies may be present or send their authorized representative at the time of opening the sealed tender box.




O.C., Buildings,
Lalbazar.

PERCENTAGE RATE TENDER AND CONTRACT FOR WORKS: GENERAL RULES
AND DIRECTIONS FOR THE GUIDANCE OF CONTRACTS.

1. All works proposed for execution by contract will be notified in a form of invitation of tender posted in public places and signed by the OC, Buildings Office, Lalbazar.

This form will state the work to be carried out, as well as the date of submitting and opening of tenders and the time allowed for carrying out the work, design and drawings and any other documents required in connection with work signed for the purpose of identification by the OC, Buildings Office, Lalbazar shall also be open for inspection by the contractor at the office of the OC, Building, Lalbazar during office hours.

2. In the event of the quotation being submitted by a firm, it must be signed separately by each member thereof or in the event of the absence of any partner it must be signed on his behalf by a person holding a power of attorney authorizing him to do so. Such power of attorney is to be produced with the tender and same in the case of a firm carried on by one member of a joint family, it must be disclose that the firm is duly registered under the Indian partnership Act.
3. Receipts for payment made on account of work, when executed by a firm, must also be signed by the several partners except where the contractors are described in their tender as a firm in which case the receipts must be signed in the name of the firm by one of the partners or by some other person having authority to give effectual receipts for the firm.
4. Any person who submits a tender shall fill up the usual printed form, stating at what rate he is willing to undertake each item of the work. Tenders which propose any alteration, in the work specified in the said form of invitation of tenders or in the time allowed for carrying out the work, or which contain any other conditions of any sort, will be liable to rejection. No single tender shall include more than one work but contractors who wish to quote for two or more works shall submit a separate tender for each. Tenders shall have the name and number of the work to which they refer written outside the envelope.
5. The Committee will open tenders in the presence of any intending contractors who may present at the time and will enter the amounts of the several tenders in a comparative statement in a suitable form.
6. The accepting authority reserves the right to reject any or all the tender without assigning any reasons and he will not be bound to accept either the lowest tender or any of the tenders.


O.C., Buildings,
Lalbazar.