

Government of West Bengal
Office of the Commissioner of Police
18, Lalbazar Street, Kolkata-700 001.

No. T-169/Gen/26-27

Date – 27. 08. 2026

NOTICE INVITING TENDER

Sealed tenders in printed form are invited for the following works from eligible tenderers as per particulars given below :

1. Name of work : Necessary ceiling repairing and painting work at Account Section of HA Office of Central Division on 2nd floor at 138, S. N. Banerjee Raod, Kolkata.
(Details Estimate annexed)
2. Eligibility : All bonafide contractors /firms having experience / valid license for this type of field.
3. Estimated Cost : Rs. 75,280/-
4. Last date for submission of the tender : **07. 09. 2026 up to 15.00 hrs.**
5. Time allowed for completion of works : 10(ten) days after the issue of Work Order.
6. The intending tenderers may inspect the site on any working day during office time.
7. The intending tenderers will have to submit copy of valid Certificate of up to date Clearance of Trade License, Elec. Contractors License, Professional Tax, Income Tax, G.S.T and Credential along with tender papers for the work and tenderers must quote percentage rate of tender in the annexed estimate .
8. Sealed Tender addressed to The Commissioner of Police, 18, Lalbazar Street, Kolkata-700001 may be dropped in the box kept in front of the office of the Officer-in-Charge, Building Section, 2nd floor, Northern Building and also in the Drop Box kept beside In Gate, Lalbazar at 18, Lalbazar Street, Kolkata-700001 before the last date.
9. Sealed tender may also be sent by Registered Post / Speed Post superscribing the envelope as “Tender in response to Tender Notice No. T-169/Gen/26-27 dt. 25.08. 2026” so as to reach this office on or before the last date & time.


O.C. Buildings,
Lalbazar, Kolkata.

ESTIMATE

Work: Necessary ceiling repairing and painting work at Account section of HA Office of Central Division within 2nd floor of 138, S. N. Road, Kolkata-700013.

Page & Item No	Description of item	Quantity	Rate	Unit	Amount	
Page-23 Item-3	Making one set of scaffolding only for replacing glass panels, painting, uprooting plant and another repairing works of building and S&P works for external works only with 10 cm. dia bamboo as main posts at the rate of 1 metre centre to centre and 7.5 cm. dia bamboo ties @ 0.75 metre apart fitting and fixing with necessary coir, nails etc. as per direction of the Engineer-in-charge. (This item should be executed only after prior approval of the Engineer-in-charge). Firstly, one number to be paid and then labour rate for shifting up to further nineteenth (19) times @ 10% each time to be considered. If necessary further after twenty times of total use, another one number new and labour rate for shifting to be considered accordingly.					
	a) 3.90 metre height	1.00	Each	279.00	Each	279.00
	(b) Extra for additional 3.6 height or part thereof	4.00	Each	245.00	Each	980.00
2 Page-11 Item-10	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	10.50	Sqmtr.	19.00	Sqmtr.	199.50
3 Page-10 Item-2	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m	0.31	Cum	939.00	Cum	291.56
4 Page-45 Item-5	Cleaning the concrete surface by removing dirt and debris, marking defective locations and removing loose concrete by careful stripping untill hard surface is exposed, cutting the concrete to regular shape, wire brushing the exposed surface and removing debris from site complete as per direction of the Engineer - in - Charge	6.21	Sqmtr.	90.00	Sqmtr.	558.90
5 Page-45 Item-6	Cleaning the exposed reinforcement preferably upto full diameter by wire brush, applying two coats of polymer based rust removing compound left for 24 hours, removing the coating and then applying two (2) coats of polymer modified anti corrosive protective coating formulated to inhibit the corrosion of reinforcement as per manufacturer's specification]	0.78	Sqmtr.	782.00	Sqmtr.	606.21
6 Page-40 Item-27	Cement concrete (1:1.5:3) with graded stone chips 5.6 mm size with hexagonal square mesh wire netting, I.R.C. fabric mesh or X.P. M. fitted and fixed after tying the existing reinforcement on concrete without distributing the same and with proper scarping and cleaning the reinforcement and disturbed concrete with wire brush etc. after applying a coat of cement including the cost of wire netting I.R.C or X. P. M. & cost of all handling and scaffolding complete as per direction of Engineer-in -charge. a) 20 mm thick	6.21	Sqmtr.	491.00	Sqmtr.	3049.11
7 Page-45 Item-8	(b) Applying 2 coats of Non-Toxic Acrylic Polymer modified Paint having adhesive & waterproofing properties by mixing in proportion (1 liquid: 4 cementitious material) or as per manufacturer's specification for water proofing layer in water tank etc. (No Departmental Cement is required)	6.21	Sqmtr.	258.00	Sqmtr.	1602.18
8 Page-189 Item-1	Plaster (to wall, Noor, ceiling etc.) with sand and cement mortar including round of or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/ staging where necessary (Ground floor).(Excluding cost of chipping over concrete surface). (ii) With 1:4 cement mortar (c) 10 mm thick plaster	16.71	Sqmtr.	133.00	Sqmtr.	2222.00

		Galvanised corrugated iron sheet work (excluding the supporting frame work) fitted and fixed with 10 mm. dia J or L hook-bolts, limpet and bitumen washers and putty complete with 150 mm. end lap and one corrugation minimum side lap. (Payment to be made on area of finished work)(GCI sheet to be supplied by contractor).	36.05	Sqmtr.	619.00	Sqmtr.	22318.00
		(i) In Roof:- a) With 0.60 mm thick sheet					
Page-158 Item-3		(A) Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 6 mm thick High Pressure Steam Cured Non Asbestos Fibre Cement Standard Ceiling Board (Density > 1300 Kg/m3) of size 595 mm X 595 mm, conforming IS 14862 & Type B Category III of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge. In ground Floor. a) False Ceiling (with 6mm thick Fibre Cement Designer Board and E-Grid T-2430).	28.14	Sqmtr.	686.00	Sqmtr.	19306.80
11 Page-204 Item-5 (b)		(b) Rendering the surface of walls and ceiling with white cement based wall putty of approved make and brand (1.5mm thick)	16.71	Sqmtr.	110.00	Sqmtr.	1838.10
12 Page-203 Item-1		Removing loose scales, blisters etc. from old painted surface and thoroughly smoothening the surface to make the same suitable for receiving fresh coat of paint.	37.98	Sqmtr.	21.00	Sqmtr.	797.62
13 Page-196 Item-10		Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats	54.69	Sqmtr.	70.00	Sqmtr.	3828.42
14 Page-200 Item-1		(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	7.96	Sqmtr.	38.00	Sqmtr.	302.63
15 Page-200 Item-2		(a) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (a) On timber or plastered surface : (iv) Two coats (with any shade except white)	7.96	Sqmtr.	81.00	Sqmtr.	645.09
16 Page-250 Item-27		Providing and fixing exterior quality Aluminium Composite Panel (ACP) wall cladding on existing Al. /MS frame work with GI brackets, ACP fixed on the existing frame work by folding the edges of ACP panel (Engraving the rear surface of ACP sheet) with CP angles, cleats and stainless Steel screws forming grooves at the periphery of ACP panel. Such grooves filled with foam and silicon sealant etc. complete with all materials (but excluding the cost of silicon sealant), labour, scaffolding and all other incidental charges e.g. VAT, Labour cess etc complete in all respect as per specification and direction of Engineer-in-charge. (Mode of payment is on finished surface area of ACP) (b) 4mm thick (0.50mm Al.+3.0mm LDPE +0.50mm Al. PVDF coating)	2.00	Sqmtr.	81.00	Sqmtr.	162.00

18 Page- 70
Item-23
(S & P)

Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992

(ii) Double Socketed 3 Meter Length. (b)110 mm	3.00	Mtr.	315.00	Mtr.	945.00
(C) Rubber Lubricant 500 ML	1.00	500 ML	187.00	500 ML	187.00
(D) Solvent Cement 250 ML	1.00	250 ML	103.00	250 ML	103.00
(B) Fittings					

19 Page- 68
Item-24
(S & P)

x) Bend 87.5° (a)75 mm	2.00	Each	61.00	Each	122.00
Labour for fitting and fixing U.P.V.C. pipes for above ground work including cost of jointing materials etc. fitting and fixing all necessary specials, cutting pipes, cutting holes in walls or R.C. floor where necessary and mending good all damages excluding the cost of masonry or concrete work, if necessary, but including the cost and fitting and fixing holder bat clamps (any floor) or for underground work including cutting trenches upto 1.5 metre and refilling the same complete as per direction of the Engineer-in-charge. (Payment will be made on centre line measurement of the total pipeline including specials. (B)Under ground (ii) 110 mm dia.	3.00	Mtr.	57.00	Mtr.	171.00

20 Page- 36
Item-3
(S & P)

Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete, C.I. brackets including two coats of painting to bracket etc.	1.00	Each	1015.00	Each	1015.00
--	------	------	---------	------	---------

21 Page- 3
Item-3
(S & P)

Supplying, fitting and fixing (f) hand Shower(Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar).	1.00	Each	1251.00	Each	1251.00
--	------	------	---------	------	---------

22 Page- 82
Item- 22
(S & P)

Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (i) 25 mm dia. and 450 mm long	1.00	Each	384.00	Each	384.00
--	------	------	--------	------	--------

	63165.12
Add 9% for CGST	5684.86
Add 9% for SGST	5684.86
Total	74534.84
Add 1% L W Cess	745.35
Grand Total	75280.18
Say	75280.00

RUPEES: SEVENTY-FIVE THOUSAND TWO HUNDRED EIGHTY ONLY.

Technically Checked & Verified

[Signature]
19/08/2016
Assistant Engineer
Kolkata Police Directorate
Govt. of West Bengal

TERMS AND CONDITON OF TENDERS

1. All works to be carried out in a manner according to specification for original work now in laid as the regional works in building department circle.
2. All materials, tools, plant and labour, the housing, water supply and transport will have to be provided by Contractor at their own cost inclusive of G.S.T. and other charges.
3. No extra work will be allowed without prior approval.
4. The contractors are requested to inspect the schedule of nature of works at site to save all eventualities connection with works any other information may be obtained from the OC, Buildings Office, Lalbazar. Any place of ignorance after submission of tender by the contractors will not be considered.
5. The quantities as shown against the item of work can be verified according to nature of works. Actual requirement to be done soon after containing the written approval of the Jt. CP(O), but contractors are liable for execution of varied quantities at their accepted rates. The rate of the addition item which are not found in the enclosed schedule will be based on building schedule of the regional works and buildings circle subject to approval of proper authority.
6. The contractors should submit tender enclosed with Trade License, Income Tax return, GST, Credential, Under taking of black listed failure to which will be disqualified.
7. The work will be taken up within 07(Seven) days after receipt of work order, failing to which legal action may be taken against the firm.
8. The Commissioner of Police Kolkata reserves the right to reject any/or all the tender rates without assigning any reason and also to distribute the said works among the tenders . There is no guarantee that the lowest tender will be accepted by the authority concern.
9. Tender addressed to the Commissioner of Police, Kolkata should be sent in a sealed cover super scribed name of tender to be dropped in the sealed TENDER BOX to be kept the OC, Buildings Office, Lalbazar at 18, Lalbazar Street, Kolkata-700 001 within 15.00 hrs on last date.
10. The Tender Committee will open the sealed tender in the Committee Room of Lalbazar, The Agencies may be present or send their authorized representative at the time of opening the sealed tender box.



O.C., Buildings,
Lalbazar.

PERCENTAGE RATE TENDER AND CONTRACT FOR WORKS: GENERAL RULES
AND DIRECTIONS FOR THE GUIDANCE OF CONTRACTS.

1. All works proposed for execution by contract will be notified in a form of invitation of tender posted in public places and signed by the OC, Buildings Office, Lalbazar.

This form will state the work to be carried out, as well as the date of submitting and opening of tenders and the time allowed for carrying out the work, design and drawings and any other documents required in connection with work signed for the purpose of identification by the OC, Buildings Office, Lalbazar shall also be open for inspection by the contractor at the office of the OC, Building, Lalbazar during office hours.

2. In the event of the quotation being submitted by a firm, it must be signed separately by each member thereof or in the event of the absence of any partner it must be signed on his behalf by a person holding a power of attorney authorizing him to do so. Such power of attorney is to be produced with the tender and same in the case of a firm carried on by one member of a joint family, it must be disclose that the firm is duly registered under the Indian partnership Act.
3. Receipts for payment made on account of work, when executed by a firm, must also be signed by the several partners except where the contractors are described in their tender as a firm in which case the receipts must be signed in the name of the firm by one of the partners or by some other person having authority to give effectual receipts for the firm.
4. Any person who submits a tender shall fill up the usual printed form, stating at what rate he is willing to undertake each item of the work. Tenders which propose any alteration, in the work specified in the said form of invitation of tenders or in the time allowed for carrying out the work, or which contain any other conditions of any sort, will be liable to rejection. No single tender shall include more than one work but contractors who wish to quote for two or more works shall submit a separate tender for each. Tenders shall have the name and number of the work to which they refer written outside the envelope.
5. The Committee will open tenders in the presence of any intending contractors who may present at the time and will enter the amounts of the several tenders in a comparative statement in a suitable form.
6. The accepting authority reserves the right to reject any or all the tender without assigning any reasons and he will not be bound to accept either the lowest tender or any of the tenders.


O.C., Buildings,
Lalbazar.